

Project :- 365 Bow Mountain Rd, Boulder, CO

Location :- Boulder, CO

Estimate Date :- 08th March 2021

Estimator :- Teesbee Consultancy

Roofing Takeoff

	Description	Unit	Quantity	Unit Rate	Amount
	Deck				
	D1 -Deck				-
1	1-1/2" x 24" x 24" Concrete pavers	Sq.ft	889		
2	Adjustable pedestals Carlisle	Sq.ft	889		-
3	Adhered TPO 60mil Waterproof Membrane As Per Manufacturer	Sq.ft	889		
4	Tapered Carlisle Secureshield	Sq.ft	889		-
5	Polyiso Rigid Insulation	Sq.ft	889		-
	Roofing				
6	R1 - Class A, Typ: Standing Seam Metal Roofing	Sq.ft	878		-
7	R2 -Class A, Typ: Carlisle TPO Waterproof Membrane as Per Manuf, Tapered Carlisle Secureshield Polyiso Rigid Insulation	Sq.ft	826		-
8	Green roof - vegetated green roof modules on pedestal system over Continuous EPDM Membrane	Sq.ft	250		-
9	3'-0" x 4'-0" Skylight (24 Sq.ft)	Nos	2		-
10	Gutter	L.ft	76		-
11	4" Wide x 4" Tall Thru wall opening to Scupper to Downspout	Nos	2		-
12	12" Wide x 4" Tall Overflow drain Thru wall opening	Nos	2		-
13	Roof drain	Nos	1		-
14	6" x 1'-6" Scupper	Nos	2		-
15	Collector Head	Nos	2		
16	Overflow drain	Nos	2		
17	Internal gutter/Drain	L.ft	5		
18	Downspouts - 10'-0" Length	Nos	5		

Roofing Takeoff

	Description	Unit	Quantity	Unit Rate	Amount
19	Downspouts - 12'-6" Length	Nos	1		
20	Downspouts - 22'-6" Length	Nos	2		
21	Downspouts - 4'-6" Length	Nos	5		
22	Downspouts - 9'-0" Length	Nos	1		
23	Roof Fascia	L.ft	43		
	Metal Flashing				
24	Metal flashing around chimney (Assumed)	L.ft	18		
25	Flashing-Standing Seam Metal roof	L.ft	54		
26	Gutter- on Green Roof	L.ft	43		
27	Metal Edge Flashing-on Green Roof	L.ft	43		
28	Metal Flashing-Roof & Wall Edge- on Green Roof	L.ft	46		
	Sub Total				-
	Insurance		3%		-
	Overhead and Profit		22%		-
	Total Amount				-

