

**Project Name :- City view Tower at Court Square**

**Location :- 3 Ct Square W, Long Island City, NY**

**Estimator :- Tesbee Consultancy**

### Masonry Estimate

Description	Unit	QTY	Material Rate	Material Amount	Labor Rate	Labor Amount	Unit Rate	Amount
<b>Celler</b>								
<b>Concrete Masonry Wall</b>								
8" Concrete Masonry Wall (3 Hr UL-U-904)	Sq.Ft	3,692	5.40	19,936.80	13.60	50,211.20	19.00	70,148.00
8" Concrete Masonry Wall	Sq.Ft	15,444	4.30	66,409.20	13.00	200,772.00	17.30	267,181.20
<b>Lintel</b>								
8" Lintel	L.F	143	9.00	1,287.00	33.00	4,719.00	42.00	6,006.00
<b>Bond Beam</b>								
8" Bond Beam	L.F	1,472	5.00	7,360.00	17.00	25,024.00	22.00	32,384.00
<b>Ground Floor/1st Floor</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	195	3.80	741.00	12.70	2,476.50	16.50	3,217.50
8" Concrete Masonry Wall (3 Hr UL-U-904)	Sq.Ft	1,305	5.40	7,047.00	13.60	17,748.00	19.00	24,795.00
8" Concrete Masonry Wall	Sq.Ft	20,295	4.30	87,268.50	13.00	263,835.00	17.30	351,103.50
<b>Lintel</b>								
8" Lintel	L.F	85	9.00	760.50	33.00	2,788.50	42.00	3,549.00
<b>Bond Beam</b>								
6" Bond Beam	L.F	13	4.70	61.10	15.80	205.40	20.50	266.50
8" Bond Beam	L.F	1,440	5.00	7,200.00	17.00	24,480.00	22.00	31,680.00
<b>2nd Floor</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	162	3.80	615.60	12.70	2,057.40	16.50	2,673.00
8" Concrete Masonry Wall	Sq.Ft	10,080	4.30	43,344.00	13.00	131,040.00	17.30	174,384.00
8" C.M.U Wall	Sq.Ft	3,672	4.30	15,789.60	12.70	46,634.40	17.00	62,424.00
<b>Lintel</b>								
8" Lintel	L.F	42	9.00	374.40	33.00	1,372.80	42.00	1,747.20
<b>Bond Beam</b>								
6" Bond Beam	L.F	9	4.70	42.30	15.80	142.20	20.50	184.50
8" Bond Beam	L.F	764	5.00	3,820.00	17.00	12,988.00	22.00	16,808.00
<b>3rd Floor</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	2,387	3.80	9,070.60	12.70	30,314.90	16.50	39,385.50
8" Concrete Masonry Wall	Sq.Ft	6,534	4.30	28,096.20	13.00	84,942.00	17.30	113,038.20
8" Concrete Masonry Wall	Sq.Ft	1,309	4.30	5,628.70	13.00	17,017.00	17.30	22,645.70
<b>Lintel</b>								
8" Lintel	L.F	29	9.00	257.40	33.00	943.80	42.00	1,201.20
8" Lintel	L.F	4	9.00	35.10	33.00	128.70	42.00	163.80
6" Lintel	L.F	5	7.20	37.44	31.80	165.36	39.00	202.80
<b>Bond Beam</b>								
6" Bond Beam	L.F	217	4.70	1,019.90	15.80	3,428.60	20.50	4,448.50
8" Bond Beam	L.F	713	5.00	3,565.00	17.00	12,121.00	22.00	15,686.00
<b>4th Floor</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	163	3.80	617.50	12.70	2,063.75	16.50	2,681.25
8" Concrete Masonry Wall	Sq.Ft	9,300	4.30	39,990.00	13.00	120,900.00	17.30	160,890.00
8" Concrete Masonry Wall	Sq.Ft	363	4.30	1,558.75	13.00	4,712.50	17.30	6,271.25
<b>Lintel</b>								
8" Lintel	L.F	34	9.00	304.20	33.00	1,115.40	42.00	1,419.60
6" Lintel	L.F	5	7.20	37.44	31.80	165.36	39.00	202.80
<b>Bond Beam</b>								
6" Bond Beam	L.F	13	4.70	61.10	15.80	205.40	20.50	266.50
8" Bond Beam	L.F	773	5.00	3,865.00	17.00	13,141.00	22.00	17,006.00
<b>5th Floor</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	143	3.80	543.40	12.70	1,816.10	16.50	2,359.50

### Masonry Estimate

Description	Unit	QTY	Material Rate	Material Amount	Labor Rate	Labor Amount	Unit Rate	Amount
8" Concrete Masonry Wall	Sq.Ft	3,311	4.30	14,237.30	13.00	43,043.00	17.30	57,280.30
8" Concrete Block	Sq.Ft	165	7.00	1,155.00	14.00	2,310.00	21.00	3,465.00
<b>Lintel</b>								
6" Lintel	L.F	5	7.20	37.44	31.80	165.36	39.00	202.80
<b>Bond Beam</b>								
6" Bond Beam	L.F	13	4.70	61.10	15.80	205.40	20.50	266.50
8" Bond Beam	L.F	316	5.00	1,580.00	17.00	5,372.00	22.00	6,952.00
<b>6th Floor</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	242	3.80	919.60	12.70	3,073.40	16.50	3,993.00
8" Concrete Masonry Wall	Sq.Ft	3,388	4.30	14,568.40	13.00	44,044.00	17.30	58,612.40
8" Concrete Block	Sq.Ft	165	7.00	1,155.00	14.00	2,310.00	21.00	3,465.00
<b>Concrete Masonry Wall</b>								
8" Lintel	L.F	5	9.00	46.80	33.00	171.60	42.00	218.40
6" Lintel	L.F	5	7.20	37.44	31.80	165.36	39.00	202.80
<b>Bond Beam</b>								
6" Bond Beam	L.F	22	4.70	103.40	15.80	347.60	20.50	451.00
8" Bond Beam	L.F	323	5.00	1,615.00	17.00	5,491.00	22.00	7,106.00
<b>7th Floor</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	154	3.80	585.20	12.70	1,955.80	16.50	2,541.00
8" Concrete Masonry Wall	Sq.Ft	1,661	4.30	7,142.30	13.00	21,593.00	17.30	28,735.30
8" Concrete Block	Sq.Ft	165	7.00	1,155.00	14.00	2,310.00	21.00	3,465.00
<b>Lintel</b>								
6" Lintel	L.F	5	7.20	37.44	31.80	165.36	39.00	202.80
<b>Bond Beam</b>								
6" Bond Beam	L.F	14	4.70	65.80	15.80	221.20	20.50	287.00
8" Bond Beam	L.F	166	5.00	830.00	17.00	2,822.00	22.00	3,652.00
<b>8th Floor</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	117	3.80	444.60	12.70	1,485.90	16.50	1,930.50
8" Concrete Masonry Wall	Sq.Ft	414	4.30	1,780.20	13.00	5,382.00	17.30	7,162.20
8" Concrete Block	Sq.Ft	135	7.00	945.00	14.00	1,890.00	21.00	2,835.00
<b>Lintel</b>								
6" Lintel	L.F	4	7.20	28.08	31.80	124.02	39.00	152.10
<b>Bond Beam</b>								
6" Bond Beam	L.F	13	4.70	61.10	15.80	205.40	20.50	266.50
8" Bond Beam	L.F	61	5.00	305.00	17.00	1,037.00	22.00	1,342.00
<b>9th Floor</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	117	3.80	444.60	12.70	1,485.90	16.50	1,930.50
8" Concrete Masonry Wall	Sq.Ft	414	4.30	1,780.20	13.00	5,382.00	17.30	7,162.20
8" Concrete Block	Sq.Ft	135	7.00	945.00	14.00	1,890.00	21.00	2,835.00
<b>Lintel</b>								
6" Lintel	L.F	4	7.20	28.08	31.80	124.02	39.00	152.10
<b>Bond Beam</b>								
6" Bond Beam	L.F	13	4.70	61.10	15.80	205.40	20.50	266.50
8" Bond Beam	L.F	61	5.00	305.00	17.00	1,037.00	22.00	1,342.00
<b>10th Floor</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	117	3.80	444.60	12.70	1,485.90	16.50	1,930.50
8" Concrete Masonry Wall	Sq.Ft	414	4.30	1,780.20	13.00	5,382.00	17.30	7,162.20
8" Concrete Block	Sq.Ft	135	7.00	945.00	14.00	1,890.00	21.00	2,835.00
<b>Lintel</b>								
6" Lintel	L.F	4	7.20	28.08	31.80	124.02	39.00	152.10
<b>Bond Beam</b>								
6" Bond Beam	L.F	13	4.70	61.10	15.80	205.40	20.50	266.50
8" Bond Beam	L.F	61	5.00	305.00	17.00	1,037.00	22.00	1,342.00
<b>11th Floor</b>								
<b>Concrete Masonry Wall</b>								

### Masonry Estimate

Description	Unit	QTY	Material Rate	Material Amount	Labor Rate	Labor Amount	Unit Rate	Amount
6" Concrete Masonry Wall	Sq.Ft	117	3.80	444.60	12.70	1,485.90	16.50	1,930.50
8" Concrete Masonry Wall	Sq.Ft	414	4.30	1,780.20	13.00	5,382.00	17.30	7,162.20
8" Concrete Block	Sq.Ft	135	7.00	945.00	14.00	1,890.00	21.00	2,835.00
<b>Lintel</b>								
6" Lintel	L.F	4	7.20	28.08	31.80	124.02	39.00	152.10
<b>Bond Beam</b>								
6" Bond Beam	L.F	13	4.70	61.10	15.80	205.40	20.50	266.50
8" Bond Beam	L.F	61	5.00	305.00	17.00	1,037.00	22.00	1,342.00
<b>12th Floor</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	117	3.80	444.60	12.70	1,485.90	16.50	1,930.50
8" Concrete Masonry Wall	Sq.Ft	414	4.30	1,780.20	13.00	5,382.00	17.30	7,162.20
8" Concrete Block	Sq.Ft	135	7.00	945.00	14.00	1,890.00	21.00	2,835.00
<b>Lintel</b>								
6" Lintel	L.F	4	7.20	28.08	31.80	124.02	39.00	152.10
<b>Bond Beam</b>								
6" Bond Beam	L.F	13	4.70	61.10	15.80	205.40	20.50	266.50
8" Bond Beam	L.F	61	5.00	305.00	17.00	1,037.00	22.00	1,342.00
<b>13th Floor</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	117	3.80	444.60	12.70	1,485.90	16.50	1,930.50
8" Concrete Masonry Wall	Sq.Ft	414	4.30	1,780.20	13.00	5,382.00	17.30	7,162.20
8" Concrete Block	Sq.Ft	135	7.00	945.00	14.00	1,890.00	21.00	2,835.00
<b>Lintel</b>								
6" Lintel	L.F	4	7.20	28.08	31.80	124.02	39.00	152.10
<b>Bond Beam</b>								
6" Bond Beam	L.F	13	4.70	61.10	15.80	205.40	20.50	266.50
8" Bond Beam	L.F	61	5.00	305.00	17.00	1,037.00	22.00	1,342.00
<b>14th Floor</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	117	3.80	444.60	12.70	1,485.90	16.50	1,930.50
8" Concrete Masonry Wall	Sq.Ft	414	4.30	1,780.20	13.00	5,382.00	17.30	7,162.20
8" Concrete Block	Sq.Ft	135	7.00	945.00	14.00	1,890.00	21.00	2,835.00
<b>Lintel</b>								
6" Lintel	L.F	4	7.20	28.08	31.80	124.02	39.00	152.10
<b>Bond Beam</b>								
6" Bond Beam	L.F	13	4.70	61.10	15.80	205.40	20.50	266.50
8" Bond Beam	L.F	61	5.00	305.00	17.00	1,037.00	22.00	1,342.00
<b>15th Floor</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	117	3.80	444.60	12.70	1,485.90	16.50	1,930.50
8" Concrete Masonry Wall	Sq.Ft	414	4.30	1,780.20	13.00	5,382.00	17.30	7,162.20
8" Concrete Block	Sq.Ft	135	7.00	945.00	14.00	1,890.00	21.00	2,835.00
<b>Lintel</b>								
6" Lintel	L.F	4	7.20	28.08	31.80	124.02	39.00	152.10
<b>Bond Beam</b>								
6" Bond Beam	L.F	13	4.70	61.10	15.80	205.40	20.50	266.50
8" Bond Beam	L.F	61	5.00	305.00	17.00	1,037.00	22.00	1,342.00
<b>16th Floor</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	117	3.80	444.60	12.70	1,485.90	16.50	1,930.50
8" Concrete Masonry Wall	Sq.Ft	414	4.30	1,780.20	13.00	5,382.00	17.30	7,162.20
8" Concrete Block	Sq.Ft	135	7.00	945.00	14.00	1,890.00	21.00	2,835.00
<b>Lintel</b>								
6" Lintel	L.F	4	7.20	28.08	31.80	124.02	39.00	152.10
<b>Bond Beam</b>								
6" Bond Beam	L.F	13	4.70	61.10	15.80	205.40	20.50	266.50
8" Bond Beam	L.F	61	5.00	305.00	17.00	1,037.00	22.00	1,342.00
<b>17th Floor</b>								
<b>Concrete Masonry Wall</b>								

### Masonry Estimate

Description	Unit	QTY	Material Rate	Material Amount	Labor Rate	Labor Amount	Unit Rate	Amount
6" Concrete Masonry Wall	Sq.Ft	117	3.80	444.60	12.70	1,485.90	16.50	1,930.50
8" Concrete Masonry Wall	Sq.Ft	414	4.30	1,780.20	13.00	5,382.00	17.30	7,162.20
8" Concrete Block	Sq.Ft	135	7.00	945.00	14.00	1,890.00	21.00	2,835.00
<b>Lintel</b>								
6" Lintel	L.F	4	7.20	28.08	31.80	124.02	39.00	152.10
<b>Bond Beam</b>								
6" Bond Beam	L.F	13	4.70	61.10	15.80	205.40	20.50	266.50
8" Bond Beam	L.F	61	5.00	305.00	17.00	1,037.00	22.00	1,342.00
<b>18th Floor</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	117	3.80	444.60	12.70	1,485.90	16.50	1,930.50
8" Concrete Masonry Wall	Sq.Ft	414	4.30	1,780.20	13.00	5,382.00	17.30	7,162.20
8" Concrete Block	Sq.Ft	135	7.00	945.00	14.00	1,890.00	21.00	2,835.00
<b>Lintel</b>								
6" Lintel	L.F	4	7.20	28.08	31.80	124.02	39.00	152.10
<b>Bond Beam</b>								
6" Bond Beam	L.F	13	4.70	61.10	15.80	205.40	20.50	266.50
8" Bond Beam	L.F	61	5.00	305.00	17.00	1,037.00	22.00	1,342.00
<b>19th Floor</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	117	3.80	444.60	12.70	1,485.90	16.50	1,930.50
8" Concrete Masonry Wall	Sq.Ft	414	4.30	1,780.20	13.00	5,382.00	17.30	7,162.20
8" Concrete Block	Sq.Ft	135	7.00	945.00	14.00	1,890.00	21.00	2,835.00
<b>Lintel</b>								
6" Lintel	L.F	4	7.20	28.08	31.80	124.02	39.00	152.10
<b>Bond Beam</b>								
6" Bond Beam	L.F	13	4.70	61.10	15.80	205.40	20.50	266.50
8" Bond Beam	L.F	61	5.00	305.00	17.00	1,037.00	22.00	1,342.00
<b>20th Floor</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	117	3.80	444.60	12.70	1,485.90	16.50	1,930.50
8" Concrete Masonry Wall	Sq.Ft	414	4.30	1,780.20	13.00	5,382.00	17.30	7,162.20
8" Concrete Block	Sq.Ft	144	7.00	1,008.00	14.00	2,016.00	21.00	3,024.00
<b>Lintel</b>								
6" Lintel	L.F	4	7.20	28.08	31.80	124.02	39.00	152.10
<b>Bond Beam</b>								
6" Bond Beam	L.F	13	4.70	61.10	15.80	205.40	20.50	266.50
8" Bond Beam	L.F	62	5.00	310.00	17.00	1,054.00	22.00	1,364.00
<b>21st Floor</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	117	3.80	444.60	12.70	1,485.90	16.50	1,930.50
8" Concrete Masonry Wall	Sq.Ft	414	4.30	1,780.20	13.00	5,382.00	17.30	7,162.20
8" Concrete Block	Sq.Ft	144	7.00	1,008.00	14.00	2,016.00	21.00	3,024.00
<b>Lintel</b>								
6" Lintel	L.F	4	7.20	28.08	31.80	124.02	39.00	152.10
<b>Bond Beam</b>								
6" Bond Beam	L.F	13	4.70	61.10	15.80	205.40	20.50	266.50
8" Bond Beam	L.F	62	5.00	310.00	17.00	1,054.00	22.00	1,364.00
<b>22ndth Floor</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	130	3.80	494.00	12.70	1,651.00	16.50	2,145.00
8" Concrete Masonry Wall	Sq.Ft	460	4.30	1,978.00	13.00	5,980.00	17.30	7,958.00
8" Concrete Block	Sq.Ft	160	7.00	1,120.00	14.00	2,240.00	21.00	3,360.00
<b>Lintel</b>								
6" Lintel	L.F	4	7.20	28.08	31.80	124.02	39.00	152.10
<b>Bond Beam</b>								
6" Bond Beam	L.F	13	4.70	61.10	15.80	205.40	20.50	266.50
8" Bond Beam	L.F	62	5.00	310.00	17.00	1,054.00	22.00	1,364.00
<b>23rd Floor</b>								
<b>Concrete Masonry Wall</b>								

### Masonry Estimate

Description	Unit	QTY	Material Rate	Material Amount	Labor Rate	Labor Amount	Unit Rate	Amount
6" Concrete Masonry Wall	Sq.Ft	117	3.80	444.60	12.70	1,485.90	16.50	1,930.50
8" Concrete Masonry Wall	Sq.Ft	414	4.30	1,780.20	13.00	5,382.00	17.30	7,162.20
8" Concrete Block	Sq.Ft	144	7.00	1,008.00	14.00	2,016.00	21.00	3,024.00
<b>Lintel</b>								
6" Lintel	L.F	4	7.20	28.08	31.80	124.02	39.00	152.10
<b>Bond Beam</b>								
6" Bond Beam	L.F	13	4.70	61.10	15.80	205.40	20.50	266.50
8" Bond Beam	L.F	62	5.00	310.00	17.00	1,054.00	22.00	1,364.00
<b>24th Floor</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	117	3.80	444.60	12.70	1,485.90	16.50	1,930.50
8" Concrete Masonry Wall	Sq.Ft	414	4.30	1,780.20	13.00	5,382.00	17.30	7,162.20
8" Concrete Block	Sq.Ft	144	7.00	1,008.00	14.00	2,016.00	21.00	3,024.00
<b>Lintel</b>								
6" Lintel	L.F	4	7.20	28.08	31.80	124.02	39.00	152.10
<b>Bond Beam</b>								
6" Bond Beam	L.F	13	4.70	61.10	15.80	205.40	20.50	266.50
8" Bond Beam	L.F	62	5.00	310.00	17.00	1,054.00	22.00	1,364.00
<b>25th Floor</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	117	3.80	444.60	12.70	1,485.90	16.50	1,930.50
8" Concrete Masonry Wall	Sq.Ft	414	4.30	1,780.20	13.00	5,382.00	17.30	7,162.20
8" Concrete Block	Sq.Ft	144	7.00	1,008.00	14.00	2,016.00	21.00	3,024.00
<b>Lintel</b>								
6" Lintel	L.F	4	7.20	28.08	31.80	124.02	39.00	152.10
<b>Bond Beam</b>								
6" Bond Beam	L.F	13	4.70	61.10	15.80	205.40	20.50	266.50
8" Bond Beam	L.F	62	5.00	310.00	17.00	1,054.00	22.00	1,364.00
<b>26th Floor</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	117	3.80	444.60	12.70	1,485.90	16.50	1,930.50
8" Concrete Masonry Wall	Sq.Ft	414	4.30	1,780.20	13.00	5,382.00	17.30	7,162.20
8" Concrete Block	Sq.Ft	144	7.00	1,008.00	14.00	2,016.00	21.00	3,024.00
<b>Lintel</b>								
6" Lintel	L.F	4	7.20	28.08	31.80	124.02	39.00	152.10
<b>Bond Beam</b>								
6" Bond Beam	L.F	13	4.70	61.10	15.80	205.40	20.50	266.50
8" Bond Beam	L.F	62	5.00	310.00	17.00	1,054.00	22.00	1,364.00
<b>27th Floor</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	117	3.80	444.60	12.70	1,485.90	16.50	1,930.50
8" Concrete Masonry Wall	Sq.Ft	414	4.30	1,780.20	13.00	5,382.00	17.30	7,162.20
8" Concrete Block	Sq.Ft	144	7.00	1,008.00	14.00	2,016.00	21.00	3,024.00
<b>Lintel</b>								
6" Lintel	L.F	4	7.20	28.08	31.80	124.02	39.00	152.10
<b>Bond Beam</b>								
6" Bond Beam	L.F	13	4.70	61.10	15.80	205.40	20.50	266.50
8" Bond Beam	L.F	62	5.00	310.00	17.00	1,054.00	22.00	1,364.00
<b>28th Floor</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	117	3.80	444.60	12.70	1,485.90	16.50	1,930.50
8" Concrete Masonry Wall	Sq.Ft	414	4.30	1,780.20	13.00	5,382.00	17.30	7,162.20
8" Concrete Block	Sq.Ft	144	7.00	1,008.00	14.00	2,016.00	21.00	3,024.00
<b>Lintel</b>								
6" Lintel	L.F	4	7.20	28.08	31.80	124.02	39.00	152.10
<b>Bond Beam</b>								
6" Bond Beam	L.F	13	4.70	61.10	15.80	205.40	20.50	266.50
8" Bond Beam	L.F	62	5.00	310.00	17.00	1,054.00	22.00	1,364.00
<b>29th Floor</b>								
<b>Concrete Masonry Wall</b>								

### Masonry Estimate

Description	Unit	QTY	Material Rate	Material Amount	Labor Rate	Labor Amount	Unit Rate	Amount
6" Concrete Masonry Wall	Sq.Ft	117	3.80	444.60	12.70	1,485.90	16.50	1,930.50
8" Concrete Masonry Wall	Sq.Ft	414	4.30	1,780.20	13.00	5,382.00	17.30	7,162.20
8" Concrete Block	Sq.Ft	144	7.00	1,008.00	14.00	2,016.00	21.00	3,024.00
<b>Lintel</b>								
6" Lintel	L.F	4	7.20	28.08	31.80	124.02	39.00	152.10
<b>Bond Beam</b>								
6" Bond Beam	L.F	13	4.70	61.10	15.80	205.40	20.50	266.50
8" Bond Beam	L.F	62	5.00	310.00	17.00	1,054.00	22.00	1,364.00
<b>30th Floor</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	117	3.80	444.60	12.70	1,485.90	16.50	1,930.50
8" Concrete Masonry Wall	Sq.Ft	414	4.30	1,780.20	13.00	5,382.00	17.30	7,162.20
8" Concrete Block	Sq.Ft	144	7.00	1,008.00	14.00	2,016.00	21.00	3,024.00
<b>Lintel</b>								
6" Lintel	L.F	4	7.20	28.08	31.80	124.02	39.00	152.10
<b>Bond Beam</b>								
6" Bond Beam	L.F	13	4.70	61.10	15.80	205.40	20.50	266.50
8" Bond Beam	L.F	62	5.00	310.00	17.00	1,054.00	22.00	1,364.00
<b>31st Floor</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	117	3.80	444.60	12.70	1,485.90	16.50	1,930.50
8" Concrete Masonry Wall	Sq.Ft	414	4.30	1,780.20	13.00	5,382.00	17.30	7,162.20
8" Concrete Block	Sq.Ft	144	7.00	1,008.00	14.00	2,016.00	21.00	3,024.00
<b>Lintel</b>								
6" Lintel	L.F	4	7.20	28.08	31.80	124.02	39.00	152.10
<b>Bond Beam</b>								
6" Bond Beam	L.F	13	4.70	61.10	15.80	205.40	20.50	266.50
8" Bond Beam	L.F	62	5.00	310.00	17.00	1,054.00	22.00	1,364.00
<b>32nd Floor</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	117	3.80	444.60	12.70	1,485.90	16.50	1,930.50
8" Concrete Masonry Wall	Sq.Ft	414	4.30	1,780.20	13.00	5,382.00	17.30	7,162.20
8" Concrete Block	Sq.Ft	144	7.00	1,008.00	14.00	2,016.00	21.00	3,024.00
<b>Lintel</b>								
6" Lintel	L.F	4	7.20	28.08	31.80	124.02	39.00	152.10
<b>Bond Beam</b>								
6" Bond Beam	L.F	13	4.70	61.10	15.80	205.40	20.50	266.50
8" Bond Beam	L.F	62	5.00	310.00	17.00	1,054.00	22.00	1,364.00
<b>33rd Floor</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	117	3.80	444.60	12.70	1,485.90	16.50	1,930.50
8" Concrete Masonry Wall	Sq.Ft	414	4.30	1,780.20	13.00	5,382.00	17.30	7,162.20
8" Concrete Block	Sq.Ft	144	7.00	1,008.00	14.00	2,016.00	21.00	3,024.00
<b>Lintel</b>								
6" Lintel	L.F	4	7.20	28.08	31.80	124.02	39.00	152.10
<b>Bond Beam</b>								
6" Bond Beam	L.F	13	4.70	61.10	15.80	205.40	20.50	266.50
8" Bond Beam	L.F	62	5.00	310.00	17.00	1,054.00	22.00	1,364.00
<b>34th Floor</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	117	3.80	444.60	12.70	1,485.90	16.50	1,930.50
8" Concrete Masonry Wall	Sq.Ft	414	4.30	1,780.20	13.00	5,382.00	17.30	7,162.20
8" Concrete Block	Sq.Ft	144	7.00	1,008.00	14.00	2,016.00	21.00	3,024.00
<b>Lintel</b>								
6" Lintel	L.F	4	7.20	28.08	31.80	124.02	39.00	152.10
<b>Bond Beam</b>								
6" Bond Beam	L.F	13	4.70	61.10	15.80	205.40	20.50	266.50
8" Bond Beam	L.F	62	5.00	310.00	17.00	1,054.00	22.00	1,364.00
<b>35th Floor</b>								
<b>Concrete Masonry Wall</b>								

### Masonry Estimate

Description	Unit	QTY	Material Rate	Material Amount	Labor Rate	Labor Amount	Unit Rate	Amount
6" Concrete Masonry Wall	Sq.Ft	143	3.80	543.40	12.70	1,816.10	16.50	2,359.50
8" Concrete Masonry Wall	Sq.Ft	506	4.30	2,175.80	13.00	6,578.00	17.30	8,753.80
8" Concrete Block	Sq.Ft	176	7.00	1,232.00	14.00	2,464.00	21.00	3,696.00
<b>Lintel</b>								
6" Lintel	L.F	4	7.20	28.08	31.80	124.02	39.00	152.10
<b>Bond Beam</b>								
6" Bond Beam	L.F	13	4.70	61.10	15.80	205.40	20.50	266.50
8" Bond Beam	L.F	62	5.00	310.00	17.00	1,054.00	22.00	1,364.00
<b>36th Floor</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	266	3.80	1,010.80	12.70	3,378.20	16.50	4,389.00
8" Concrete Masonry Wall	Sq.Ft	4,655	4.30	20,016.50	13.00	60,515.00	17.30	80,531.50
8" Concrete Block	Sq.Ft	285	7.00	1,995.00	14.00	3,990.00	21.00	5,985.00
<b>Lintel</b>								
8" Lintel	L.F	20	9.00	175.50	33.00	643.50	42.00	819.00
<b>Bond Beam</b>								
6" Bond Beam	L.F	14	4.70	65.80	15.80	221.20	20.50	287.00
8" Bond Beam	L.F	260	5.00	1,300.00	17.00	4,420.00	22.00	5,720.00
<b>37th Floor</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	220	3.80	836.00	12.70	2,794.00	16.50	3,630.00
8" Concrete Masonry Wall	Sq.Ft	1,056	4.30	4,540.80	13.00	13,728.00	17.30	18,268.80
8" Concrete Block	Sq.Ft	165	7.00	1,155.00	14.00	2,310.00	21.00	3,465.00
<b>Lintel</b>								
8" Lintel	L.F	5	9.00	46.80	33.00	171.60	42.00	218.40
<b>Bond Beam</b>								
6" Bond Beam	L.F	20	4.70	94.00	15.80	316.00	20.50	410.00
8" Bond Beam	L.F	111	5.00	555.00	17.00	1,887.00	22.00	2,442.00
<b>38th Floor</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	117	3.80	444.60	12.70	1,485.90	16.50	1,930.50
8" Concrete Masonry Wall	Sq.Ft	423	4.30	1,818.90	13.00	5,499.00	17.30	7,317.90
8" Concrete Block	Sq.Ft	135	7.00	945.00	14.00	1,890.00	21.00	2,835.00
<b>Lintel</b>								
6" Lintel	L.F	5	7.20	37.44	31.80	165.36	39.00	202.80
<b>Bond Beam</b>								
6" Bond Beam	L.F	13	4.70	61.10	15.80	205.40	20.50	266.50
8" Bond Beam	L.F	62	5.00	310.00	17.00	1,054.00	22.00	1,364.00
<b>39th Floor</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	117	3.80	444.60	12.70	1,485.90	16.50	1,930.50
8" Concrete Masonry Wall	Sq.Ft	423	4.30	1,818.90	13.00	5,499.00	17.30	7,317.90
8" Concrete Block	Sq.Ft	135	7.00	945.00	14.00	1,890.00	21.00	2,835.00
<b>Lintel</b>								
6" Lintel	L.F	5	7.20	37.44	31.80	165.36	39.00	202.80
<b>Bond Beam</b>								
6" Bond Beam	L.F	13	4.70	61.10	15.80	205.40	20.50	266.50
8" Bond Beam	L.F	62	5.00	310.00	17.00	1,054.00	22.00	1,364.00
<b>40th Floor</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	117	3.80	444.60	12.70	1,485.90	16.50	1,930.50
8" Concrete Masonry Wall	Sq.Ft	423	4.30	1,818.90	13.00	5,499.00	17.30	7,317.90
8" Concrete Block	Sq.Ft	135	7.00	945.00	14.00	1,890.00	21.00	2,835.00
<b>Lintel</b>								
6" Lintel	L.F	5	7.20	37.44	31.80	165.36	39.00	202.80
<b>Bond Beam</b>								
6" Bond Beam	L.F	13	4.70	61.10	15.80	205.40	20.50	266.50
8" Bond Beam	L.F	62	5.00	310.00	17.00	1,054.00	22.00	1,364.00
<b>41st Floor</b>								
<b>Concrete Masonry Wall</b>								

### Masonry Estimate

Description	Unit	QTY	Material Rate	Material Amount	Labor Rate	Labor Amount	Unit Rate	Amount
6" Concrete Masonry Wall	Sq.Ft	117	3.80	444.60	12.70	1,485.90	16.50	1,930.50
8" Concrete Masonry Wall	Sq.Ft	423	4.30	1,818.90	13.00	5,499.00	17.30	7,317.90
8" Concrete Block	Sq.Ft	135	7.00	945.00	14.00	1,890.00	21.00	2,835.00
<b>Lintel</b>								
6" Lintel	L.F	5	7.20	37.44	31.80	165.36	39.00	202.80
<b>Bond Beam</b>								
6" Bond Beam	L.F	13	4.70	61.10	15.80	205.40	20.50	266.50
8" Bond Beam	L.F	62	5.00	310.00	17.00	1,054.00	22.00	1,364.00
<b>42nd Floor</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	117	3.80	444.60	12.70	1,485.90	16.50	1,930.50
8" Concrete Masonry Wall	Sq.Ft	423	4.30	1,818.90	13.00	5,499.00	17.30	7,317.90
8" Concrete Block	Sq.Ft	135	7.00	945.00	14.00	1,890.00	21.00	2,835.00
<b>Lintel</b>								
6" Lintel	L.F	5	7.20	37.44	31.80	165.36	39.00	202.80
<b>Bond Beam</b>								
6" Bond Beam	L.F	13	4.70	61.10	15.80	205.40	20.50	266.50
8" Bond Beam	L.F	62	5.00	310.00	17.00	1,054.00	22.00	1,364.00
<b>43rd Floor</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	117	3.80	444.60	12.70	1,485.90	16.50	1,930.50
8" Concrete Masonry Wall	Sq.Ft	423	4.30	1,818.90	13.00	5,499.00	17.30	7,317.90
8" Concrete Block	Sq.Ft	135	7.00	945.00	14.00	1,890.00	21.00	2,835.00
<b>Lintel</b>								
6" Lintel	L.F	5	7.20	37.44	31.80	165.36	39.00	202.80
<b>Bond Beam</b>								
6" Bond Beam	L.F	13	4.70	61.10	15.80	205.40	20.50	266.50
8" Bond Beam	L.F	62	5.00	310.00	17.00	1,054.00	22.00	1,364.00
<b>44th Floor</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	117	3.80	444.60	12.70	1,485.90	16.50	1,930.50
8" Concrete Masonry Wall	Sq.Ft	423	4.30	1,818.90	13.00	5,499.00	17.30	7,317.90
8" Concrete Block	Sq.Ft	135	7.00	945.00	14.00	1,890.00	21.00	2,835.00
<b>Lintel</b>								
6" Lintel	L.F	5	7.20	37.44	31.80	165.36	39.00	202.80
<b>Bond Beam</b>								
6" Bond Beam	L.F	13	4.70	61.10	15.80	205.40	20.50	266.50
8" Bond Beam	L.F	62	5.00	310.00	17.00	1,054.00	22.00	1,364.00
<b>45th Floor</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	130	3.80	494.00	12.70	1,651.00	16.50	2,145.00
8" Concrete Masonry Wall	Sq.Ft	470	4.30	2,021.00	13.00	6,110.00	17.30	8,131.00
8" Concrete Block	Sq.Ft	150	7.00	1,050.00	14.00	2,100.00	21.00	3,150.00
<b>Lintel</b>								
6" Lintel	L.F	5	7.20	37.44	31.80	165.36	39.00	202.80
<b>Bond Beam</b>								
6" Bond Beam	L.F	13	4.70	61.10	15.80	205.40	20.50	266.50
8" Bond Beam	L.F	62	5.00	310.00	17.00	1,054.00	22.00	1,364.00
<b>46th Floor</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	117	3.80	444.60	12.70	1,485.90	16.50	1,930.50
8" Concrete Masonry Wall	Sq.Ft	423	4.30	1,818.90	13.00	5,499.00	17.30	7,317.90
8" Concrete Block	Sq.Ft	135	7.00	945.00	14.00	1,890.00	21.00	2,835.00
<b>Lintel</b>								
6" Lintel	L.F	5	7.20	37.44	31.80	165.36	39.00	202.80
<b>Bond Beam</b>								
6" Bond Beam	L.F	13	4.70	61.10	15.80	205.40	20.50	266.50
8" Bond Beam	L.F	62	5.00	310.00	17.00	1,054.00	22.00	1,364.00
<b>47th Floor</b>								
<b>Concrete Masonry Wall</b>								



### Masonry Estimate

Description	Unit	QTY	Material Rate	Material Amount	Labor Rate	Labor Amount	Unit Rate	Amount
6" Concrete Masonry Wall	Sq.Ft	117	3.80	444.60	12.70	1,485.90	16.50	1,930.50
8" Concrete Masonry Wall	Sq.Ft	423	4.30	1,818.90	13.00	5,499.00	17.30	7,317.90
8" Concrete Block	Sq.Ft	135	7.00	945.00	14.00	1,890.00	21.00	2,835.00
<b>Lintel</b>								
6" Lintel	L.F	5	7.20	37.44	31.80	165.36	39.00	202.80
<b>Bond Beam</b>								
6" Bond Beam	L.F	13	4.70	61.10	15.80	205.40	20.50	266.50
8" Bond Beam	L.F	62	5.00	310.00	17.00	1,054.00	22.00	1,364.00
<b>48th Floor</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	117	3.80	444.60	12.70	1,485.90	16.50	1,930.50
8" Concrete Masonry Wall	Sq.Ft	423	4.30	1,818.90	13.00	5,499.00	17.30	7,317.90
8" Concrete Block	Sq.Ft	135	7.00	945.00	14.00	1,890.00	21.00	2,835.00
<b>Lintel</b>								
6" Lintel	L.F	5	7.20	37.44	31.80	165.36	39.00	202.80
<b>Bond Beam</b>								
6" Bond Beam	L.F	13	4.70	61.10	15.80	205.40	20.50	266.50
8" Bond Beam	L.F	62	5.00	310.00	17.00	1,054.00	22.00	1,364.00
<b>49th Floor</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	117	3.80	444.60	12.70	1,485.90	16.50	1,930.50
8" Concrete Masonry Wall	Sq.Ft	423	4.30	1,818.90	13.00	5,499.00	17.30	7,317.90
8" Concrete Block	Sq.Ft	135	7.00	945.00	14.00	1,890.00	21.00	2,835.00
<b>Lintel</b>								
6" Lintel	L.F	5	7.20	37.44	31.80	165.36	39.00	202.80
<b>Bond Beam</b>								
6" Bond Beam	L.F	13	4.70	61.10	15.80	205.40	20.50	266.50
8" Bond Beam	L.F	62	5.00	310.00	17.00	1,054.00	22.00	1,364.00
<b>50th Floor</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	117	3.80	444.60	12.70	1,485.90	16.50	1,930.50
8" Concrete Masonry Wall	Sq.Ft	423	4.30	1,818.90	13.00	5,499.00	17.30	7,317.90
8" Concrete Block	Sq.Ft	135	7.00	945.00	14.00	1,890.00	21.00	2,835.00
<b>Lintel</b>								
6" Lintel	L.F	5	7.20	37.44	31.80	165.36	39.00	202.80
<b>Bond Beam</b>								
6" Bond Beam	L.F	13	4.70	61.10	15.80	205.40	20.50	266.50
8" Bond Beam	L.F	62	5.00	310.00	17.00	1,054.00	22.00	1,364.00
<b>51st Floor</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	117	3.80	444.60	12.70	1,485.90	16.50	1,930.50
8" Concrete Masonry Wall	Sq.Ft	432	4.30	1,857.60	13.00	5,616.00	17.30	7,473.60
8" Concrete Block	Sq.Ft	135	7.00	945.00	14.00	1,890.00	21.00	2,835.00
<b>Lintel</b>								
6" Lintel	L.F	5	7.20	37.44	31.80	165.36	39.00	202.80
<b>Bond Beam</b>								
6" Bond Beam	L.F	13	4.70	61.10	15.80	205.40	20.50	266.50
8" Bond Beam	L.F	62	5.00	310.00	17.00	1,054.00	22.00	1,364.00
<b>52nd Floor</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	117	3.80	444.60	12.70	1,485.90	16.50	1,930.50
8" Concrete Masonry Wall	Sq.Ft	432	4.30	1,857.60	13.00	5,616.00	17.30	7,473.60
8" Concrete Block	Sq.Ft	135	7.00	945.00	14.00	1,890.00	21.00	2,835.00
<b>Lintel</b>								
6" Lintel	L.F	5	7.20	37.44	31.80	165.36	39.00	202.80
<b>Bond Beam</b>								
6" Bond Beam	L.F	13	4.70	61.10	15.80	205.40	20.50	266.50
8" Bond Beam	L.F	62	5.00	310.00	17.00	1,054.00	22.00	1,364.00
<b>53rd Floor</b>								
<b>Concrete Masonry Wall</b>								

### Masonry Estimate

Description	Unit	QTY	Material Rate	Material Amount	Labor Rate	Labor Amount	Unit Rate	Amount
6" Concrete Masonry Wall	Sq.Ft	117	3.80	444.60	12.70	1,485.90	16.50	1,930.50
8" Concrete Masonry Wall	Sq.Ft	432	4.30	1,857.60	13.00	5,616.00	17.30	7,473.60
8" Concrete Block	Sq.Ft	135	7.00	945.00	14.00	1,890.00	21.00	2,835.00
<b>Lintel</b>								
6" Lintel	L.F	5	7.20	37.44	31.80	165.36	39.00	202.80
<b>Bond Beam</b>								
6" Bond Beam	L.F	13	4.70	61.10	15.80	205.40	20.50	266.50
8" Bond Beam	L.F	62	5.00	310.00	17.00	1,054.00	22.00	1,364.00
<b>54thFloor</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	117	3.80	444.60	12.70	1,485.90	16.50	1,930.50
8" Concrete Masonry Wall	Sq.Ft	432	4.30	1,857.60	13.00	5,616.00	17.30	7,473.60
8" Concrete Block	Sq.Ft	135	7.00	945.00	14.00	1,890.00	21.00	2,835.00
<b>Lintel</b>								
6" Lintel	L.F	5	7.20	37.44	31.80	165.36	39.00	202.80
<b>Bond Beam</b>								
6" Bond Beam	L.F	13	4.70	61.10	15.80	205.40	20.50	266.50
8" Bond Beam	L.F	62	5.00	310.00	17.00	1,054.00	22.00	1,364.00
<b>55thFloor</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	117	3.80	444.60	12.70	1,485.90	16.50	1,930.50
8" Concrete Masonry Wall	Sq.Ft	432	4.30	1,857.60	13.00	5,616.00	17.30	7,473.60
8" Concrete Block	Sq.Ft	135	7.00	945.00	14.00	1,890.00	21.00	2,835.00
<b>Lintel</b>								
6" Lintel	L.F	5	7.20	37.44	31.80	165.36	39.00	202.80
<b>Bond Beam</b>								
6" Bond Beam	L.F	13	4.70	61.10	15.80	205.40	20.50	266.50
8" Bond Beam	L.F	62	5.00	310.00	17.00	1,054.00	22.00	1,364.00
<b>56thFloor</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	117	3.80	444.60	12.70	1,485.90	16.50	1,930.50
8" Concrete Masonry Wall	Sq.Ft	432	4.30	1,857.60	13.00	5,616.00	17.30	7,473.60
8" Concrete Block	Sq.Ft	135	7.00	945.00	14.00	1,890.00	21.00	2,835.00
<b>Lintel</b>								
6" Lintel	L.F	5	7.20	37.44	31.80	165.36	39.00	202.80
<b>Bond Beam</b>								
6" Bond Beam	L.F	13	4.70	61.10	15.80	205.40	20.50	266.50
8" Bond Beam	L.F	62	5.00	310.00	17.00	1,054.00	22.00	1,364.00
<b>57thFloor</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	117	3.80	444.60	12.70	1,485.90	16.50	1,930.50
8" Concrete Masonry Wall	Sq.Ft	432	4.30	1,857.60	13.00	5,616.00	17.30	7,473.60
8" Concrete Block	Sq.Ft	135	7.00	945.00	14.00	1,890.00	21.00	2,835.00
<b>Lintel</b>								
6" Lintel	L.F	5	7.20	37.44	31.80	165.36	39.00	202.80
<b>Bond Beam</b>								
6" Bond Beam	L.F	13	4.70	61.10	15.80	205.40	20.50	266.50
8" Bond Beam	L.F	62	5.00	310.00	17.00	1,054.00	22.00	1,364.00
<b>58thFloor</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	117	3.80	444.60	12.70	1,485.90	16.50	1,930.50
8" Concrete Masonry Wall	Sq.Ft	432	4.30	1,857.60	13.00	5,616.00	17.30	7,473.60
8" Concrete Block	Sq.Ft	135	7.00	945.00	14.00	1,890.00	21.00	2,835.00
<b>Lintel</b>								
6" Lintel	L.F	5	7.20	37.44	31.80	165.36	39.00	202.80
<b>Bond Beam</b>								
6" Bond Beam	L.F	13	4.70	61.10	15.80	205.40	20.50	266.50
8" Bond Beam	L.F	62	5.00	310.00	17.00	1,054.00	22.00	1,364.00
<b>59thFloor</b>								
<b>Concrete Masonry Wall</b>								

### Masonry Estimate

Description	Unit	QTY	Material Rate	Material Amount	Labor Rate	Labor Amount	Unit Rate	Amount
6" Concrete Masonry Wall	Sq.Ft	117	3.80	444.60	12.70	1,485.90	16.50	1,930.50
8" Concrete Masonry Wall	Sq.Ft	432	4.30	1,857.60	13.00	5,616.00	17.30	7,473.60
8" Concrete Block	Sq.Ft	135	7.00	945.00	14.00	1,890.00	21.00	2,835.00
<b>Lintel</b>								
6" Lintel	L.F	5	7.20	37.44	31.80	165.36	39.00	202.80
<b>Bond Beam</b>								
6" Bond Beam	L.F	13	4.70	61.10	15.80	205.40	20.50	266.50
8" Bond Beam	L.F	62	5.00	310.00	17.00	1,054.00	22.00	1,364.00
<b>60th Floor</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	117	3.80	444.60	12.70	1,485.90	16.50	1,930.50
8" Concrete Masonry Wall	Sq.Ft	432	4.30	1,857.60	13.00	5,616.00	17.30	7,473.60
8" Concrete Block	Sq.Ft	135	7.00	945.00	14.00	1,890.00	21.00	2,835.00
<b>Lintel</b>								
6" Lintel	L.F	5	7.20	37.44	31.80	165.36	39.00	202.80
<b>Bond Beam</b>								
6" Bond Beam	L.F	13	4.70	61.10	15.80	205.40	20.50	266.50
8" Bond Beam	L.F	62	5.00	310.00	17.00	1,054.00	22.00	1,364.00
<b>61st Floor</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	130	3.80	494.00	12.70	1,651.00	16.50	2,145.00
8" Concrete Masonry Wall	Sq.Ft	480	4.30	2,064.00	13.00	6,240.00	17.30	8,304.00
8" Concrete Block	Sq.Ft	150	7.00	1,050.00	14.00	2,100.00	21.00	3,150.00
<b>Lintel</b>								
6" Lintel	L.F	5	7.20	37.44	31.80	165.36	39.00	202.80
<b>Bond Beam</b>								
6" Bond Beam	L.F	13	4.70	61.10	15.80	205.40	20.50	266.50
8" Bond Beam	L.F	62	5.00	310.00	17.00	1,054.00	22.00	1,364.00
<b>62nd Floor</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	159	3.80	605.15	12.70	2,022.48	16.50	2,627.63
8" Concrete Masonry Wall	Sq.Ft	404	4.30	1,738.28	13.00	5,255.25	17.30	6,993.53
8" Concrete Block	Sq.Ft	184	7.00	1,286.25	14.00	2,572.50	21.00	3,858.75
<b>Lintel</b>								
8" Lintel	L.F	5	9.00	46.80	33.00	171.60	42.00	218.40
6" Lintel	L.F	5	7.20	37.44	31.80	165.36	39.00	202.80
<b>Bond Beam</b>								
6" Bond Beam	L.F	13	4.70	61.10	15.80	205.40	20.50	266.50
8" Bond Beam	L.F	48	5.00	240.00	17.00	816.00	22.00	1,056.00
<b>63rd Floor</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	140	3.80	532.00	12.70	1,778.00	16.50	2,310.00
8" Concrete Masonry Wall	Sq.Ft	470	4.30	2,021.00	13.00	6,110.00	17.30	8,131.00
8" Concrete Block	Sq.Ft	150	7.00	1,050.00	14.00	2,100.00	21.00	3,150.00
<b>Lintel</b>								
6" Lintel	L.F	5	7.20	37.44	31.80	165.36	39.00	202.80
<b>Bond Beam</b>								
6" Bond Beam	L.F	14	4.70	65.80	15.80	221.20	20.50	287.00
8" Bond Beam	L.F	62	5.00	310.00	17.00	1,054.00	22.00	1,364.00
<b>64th Floor</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	140	3.80	532.00	12.70	1,778.00	16.50	2,310.00
8" Concrete Masonry Wall	Sq.Ft	470	4.30	2,021.00	13.00	6,110.00	17.30	8,131.00
8" Concrete Block	Sq.Ft	150	7.00	1,050.00	14.00	2,100.00	21.00	3,150.00
<b>Lintel</b>								
6" Lintel	L.F	5	7.20	37.44	31.80	165.36	39.00	202.80
<b>Bond Beam</b>								
6" Bond Beam	L.F	14	4.70	65.80	15.80	221.20	20.50	287.00
8" Bond Beam	L.F	62	5.00	310.00	17.00	1,054.00	22.00	1,364.00

### Masonry Estimate

Description	Unit	QTY	Material Rate	Material Amount	Labor Rate	Labor Amount	Unit Rate	Amount
<b>65th Floor</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	140	3.80	532.00	12.70	1,778.00	16.50	2,310.00
8" Concrete Masonry Wall	Sq.Ft	470	4.30	2,021.00	13.00	6,110.00	17.30	8,131.00
8" Concrete Block	Sq.Ft	150	7.00	1,050.00	14.00	2,100.00	21.00	3,150.00
<b>Lintel</b>								
6" Lintel	L.F	5	7.20	37.44	31.80	165.36	39.00	202.80
<b>Bond Beam</b>								
6" Bond Beam	L.F	14	4.70	65.80	15.80	221.20	20.50	287.00
8" Bond Beam	L.F	62	5.00	310.00	17.00	1,054.00	22.00	1,364.00
<b>66th Floor</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	140	3.80	532.00	12.70	1,778.00	16.50	2,310.00
8" Concrete Masonry Wall	Sq.Ft	470	4.30	2,021.00	13.00	6,110.00	17.30	8,131.00
8" Concrete Block	Sq.Ft	150	7.00	1,050.00	14.00	2,100.00	21.00	3,150.00
<b>Lintel</b>								
6" Lintel	L.F	5	7.20	37.44	31.80	165.36	39.00	202.80
<b>Bond Beam</b>								
6" Bond Beam	L.F	14	4.70	65.80	15.80	221.20	20.50	287.00
8" Bond Beam	L.F	62	5.00	310.00	17.00	1,054.00	22.00	1,364.00
<b>67th Floor</b>								
<b>Concrete Masonry Wall</b>								
8" Concrete Masonry Wall	Sq.Ft	10,530	4.30	45,279.00	13.00	136,890.00	17.30	182,169.00
8" Concrete Block	Sq.Ft	270	7.00	1,890.00	14.00	3,780.00	21.00	5,670.00
<b>Lintel</b>								
6" Lintel	L.F	35	7.20	252.72	31.80	1,116.18	39.00	1,368.90
<b>Bond Beam</b>								
8" Bond Beam	L.F	36	5.00	180.00	17.00	612.00	22.00	792.00
<b>Main Roof</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	126	3.80	478.80	12.70	1,600.20	16.50	2,079.00
8" Concrete Masonry Wall	Sq.Ft	531	4.30	2,283.30	13.00	6,903.00	17.30	9,186.30
10" Solid Concrete Masonry Wall	Sq.Ft	36	5.70	205.20	13.80	496.80	19.50	702.00
8" Concrete Block	Sq.Ft	171	7.00	1,197.00	14.00	2,394.00	21.00	3,591.00
<b>Bond Beam</b>								
8" Bond Beam	L.F	92	5.00	460.00	17.00	1,564.00	22.00	2,024.00
10" Bond Beam	L.F	4	5.40	21.60	18.00	72.00	23.40	93.60
<b>EMR Plan</b>								
<b>Concrete Masonry Wall</b>								
6" Concrete Masonry Wall	Sq.Ft	216	3.80	820.80	12.70	2,743.20	16.50	3,564.00
8" Concrete Masonry Wall	Sq.Ft	204	4.30	877.20	13.00	2,652.00	17.30	3,529.20
<b>Lintel</b>								
6" Lintel	L.F	5	7.20	37.44	31.80	165.36	39.00	202.80
<b>Bond Beam</b>								
6" Bond Beam	L.F	18	4.70	84.60	15.80	284.40	20.50	369.00
8" Bond Beam	L.F	17	5.00	85.00	17.00	289.00	22.00	374.00
<b>Total</b>				<b>698,009.78</b>		<b>2,067,495.11</b>		<b>2,765,504.90</b>
<b>Insurance</b>	<b>3%</b>							<b>82,965.15</b>
<b>Overhead and Profit</b>	<b>22%</b>							<b>608,411.08</b>
<b>Total Amount</b>				<b>872,512.23</b>		<b>2,584,368.89</b>		<b>3,456,881.12</b>

Note: Supplying the Bricks to Floors by G.C